

**SURVEY &
REMONUMENTATION**

LIBER **1810** PAGE **618**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

APR 28 1995

1994 DEC 29 AM 10:17

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11</u> R <u>16</u>	<u>M-1</u>
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

A 1642

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Stephen V. Vallier in a field survey on December, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:
1837 GLO set corner
1950's M.C.R.C. Tie Map - iron
1980 D. Schiele - L.C.R.C. Liber 1188 Page 678 - Found iron
1983 C.F. Lewandowski L.C.R.C. Liber 1271 Page 934 - Found iron.
Reset with 4" cast iron monument with County Survey Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
Found 4" cast iron monument with County Survey Cap.
Accepted position of corner due to Historical usage and consistent documentation.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
LAND SURVEYOR IN ACCORDANCE
WITH P.A. 74, OF 1970

W.C. 11/19/94 SDC

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
4" cast iron monument with County Survey Cap.

- N 85 deg W 26.13' Nail South side 14" Oak
- N 85 deg W 41.27' County Monument (L-13 T12N R16W)
- N 7 deg W 27.13' Nail West side 8" White Pine
- S 64 deg E 22.11' Nail North side Twin Oak Stump
- S 40 deg W 27.20' Nail North side 10" Oak



Signed by *Stephen Vallier* Date *Dec 27, 1994*
Surveyor's Michigan License No. 28428