

SURVEY & RE-MONUMENTATION

LIBER **1810** PAGE **655**

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECEIVED FOR RECORD

APR 28 1995

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 29 AM 10:20

COMMISSION

Carrie Carter
REGISTER OF DEEDS

For corners in

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>16W</u>	<u>M 6</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

A1679

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
6													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, Ralph W. VanRiper, in a field survey on November 18, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E 1/4 Corner of Section 13, T 11 N, R 16 W, Dalton Township

Set post May 11, 1837, by GLO Surveyors

Tamarack 10" N 80° W 65 L
Tamarack 9" S 5° W 24 L

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found steel bar as per Muskegon County Road Commission Witness book, recorded by Sammy S. Barnett, RLS #16923, Liber 1036, Page 335, May 13, 1974. Also recorded by John P. Clapp, RLS #14091, Liber 1011, Page 644, 645, and 646, April 27, 1973.

14" White Oak NE 184.1'
12" White Oak NE 176.2'
12" White Oak NE 137.1'
Power Pole NE 42.1'
Tel. Pole WSW 69.0'


POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

May 2 1994 sw

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Surveyor Cap

N 15° E 123.36' Set nail W side 12" Pine
N 40° E 41.93' Fd. nail SE side Power Pole
S 10° E 129.58' Set nail NE side 4" Birch
S 15° W 155.47' Set nail E side 12" Birch
S 55° W 74.50' Fd. nail NW side 8" Birch
N 20° W 146.23' Set nail E side 24" Pine



Signed by *Ralph W. Van Riper* Date 12/27/94
Surveyor's Michigan License No. 16946