

APR 04 1996

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in
Muskegon
(County)

Located In: Corner Code #

		11N	17W	C-9
1. Public Land Survey	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
	T	_____	_____	_____
2. Property Controlling in Section	S	_____	_____	_____
	S	_____	_____	_____
3. Miscellaneous Property in Sec.	S	_____	_____	_____
	S	_____	_____	_____

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECORDS & DEEDS
1995 FEB 18 PM 4:16
Deed in file

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Stephen V. Vallier, P.S. November 6 95

I, _____, in a field survey on _____, 19____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner	S 09 deg. E	16 Links	6" Aspen
	N 26 deg. W	11 Links	6" Aspen
1979 J. Campbell found 3/4" Iron Pipe (Record LCRC Liber 1171 Page 908)	WSW	71.05'	20" Oak
	NW	30.37'	14" Pine
	NNE	31.95'	10" Oak

(see Exhibit "A")

3. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap. Checks witnesses from Section "A"

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 315, OF 1990

Nov. 7, 1995

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap.

N 20 deg. E	83.40'	Telephone Pole
N 45 deg. E	59.20'	36" Oak
S 35 deg. E	59.68'	12" Twin Pine
W	35.20'	40" Pine
S 43 deg. W	56.01'	10" White Pine (found nail)
N 50 deg. E	64.65'	36" Oak (found nail)



Signed by Stephen V. Vallier Date 12/15/95
Surveyor's Michigan License No. 28428