

**SURVEY & REMONUMENTATION**

*A1871 Pg. 622*

**A1737**

**APR 04 1996**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in **COMMISSION**

<u>Muskegon</u> (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>17W</u>	<u>C-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF MUSKEGON  
 RECEIVED  
 1995 DEC 18 PM 4:16  
*Deed Office*

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Stephen V. Vallier, P.S. in a field survey on November 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:  
 1837 GLO set corner **12" Black Oak for Post**  
 1979 J. Campbell found 1/2" rod recorded LCRC Liber 1171 Page 908  
 SE 41.10' Power Pole  
 E 25.80' 30" Oak  
 SW 33.90' Power Pole

(see Exhibit "A")

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County survey Cap. Accept position of corner recorded in Liber 1237 Page 423. 1/2" rered was erroneously set by witnesses tie which was moved.

POSITION OF SAID  
 RECORDED CORNER  
 REVIEWED & RATIFIED  
 BY MUSKEGON COUNTY  
 PEER GROUP IN ACCORDANCE  
 WITH P.A. 345, OF 1990

*Nov. 17, 1995*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 4" x 30" Cast Iron Monument with County survey Cap.

- |             |        |                   |
|-------------|--------|-------------------|
| S 70 deg. E | 26.40' | 28" Oak (nail)    |
| S 70 deg. E | 25.75' | 28" Oak (nail)    |
| N 53 deg. E | 61.30' | 8" Oak (nail)     |
| N 35 deg. W | 90.03' | 12" Oak (nail)    |
| S 55 deg. W | 40.45' | Power Pole (nail) |
| S           | 12.08' | 1/2" Rod          |



Signed by *Stephen V. Vallier* Date 12/15/95  
 Surveyor's Michigan License No. 28428