

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon

(County)

Located in:

Corner Code #

- 1. Public Land Survey T 11N R 17W E-10
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____

SURVEY & REMONUMENTATION

APR 04 1996

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

COMMISSION

STATE OF MICHIGAN
COUNTY OF MUSKEGON
RECORDED
1995 FEB 18 PM 4:17
Coburn

I, Stephen V. Vallier, P.S. in a field survey on February 22, 1995

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO set corner S 13 deg. W 20 Links 16" Pine
- N 05 deg. E 10 Links 9" Black Oak
- 1979 FF Smith - Railroad Spike Recorded survey Liber 1230 Page 358.
- NW 81.78' 12" Oak
- NE 76.10' 8" Oak
- ESE 69.11' 24" Pine

(see Exhibit "A")

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 16" Cast Iron Monument with County survey Cap. Checked witnesses from Section "A".

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

Nov. 13, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 4" x 16" Cast Iron Monument with County Survey Cap.

- N 82 deg. W 54.16' 14" Oak (set nail)
- N 48 deg. W 81.90' 16" Oak (nail)
- N 60 deg. W 49.07' 18" Oak (nail)
- N 48 deg. E 76.17' 10" Oak (nail)
- S 84 deg. E 69.24' 20" Pine (nail)



Signed by Stephen V. Vallier
Surveyor's Michigan License No. 28428

Date 12/15/95