

A1871 Pg. 634

A1745

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon

(County)

Located In:

Corner Code #

1. Public Land Survey

T 11N R 17W

E-11

T _____ R _____

T _____ R _____

T _____ R _____

2. Property Controlling
in Section

S _____ T _____ R _____

S _____ T _____ R _____

3. Miscellaneous
Property in Sec.

S _____ T _____ R _____

S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

**SURVEY &
REMONUMENTATION**

APR 04 1996

Register of Deeds Stamp & File Number

COMMISSION

STATE OF MICHIGAN
COUNTY OF MUSKEGON
REGISTER OF DEEDS
1995 FEB 10 AM 11:17

Stephen V. Vallier, P.S.

February 22

19 95

I, _____, in a field survey on _____, 19 _____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1837 GLO set corner S 39 deg. W 30 Links 15" Spruce
N 47 deg. W 1.48 Chains 20" Spruce

1982 CF Lewandowski found Railroad Spike on top of 1 1/2" Iron Pipe. Reset 4" x 30" Cast Iron Monument with County survey Cap. Recorded LCRC Liber 1237 Page 425.

N 50 deg. W 46.52' 28" Pine (nail)
N 45 deg. E 43.67' Power Pole
S 45 deg. E 62.14' 3" Oak
S 45 deg. W 67.50' 12" Oak (nail)

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" x 30" Cast Iron Monument with County Survey Cap. Check witnesses from Section "A".

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

Nov. 13, 1995

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
Found 4" x 30" Cast Iron Monument with County Survey Cap.

N 50 deg. W 46.52' 28" Pine (nail)
N 45 deg. E 43.67' Power Pole
S 45 deg. E 62.14' 3" Oak
S 45 deg. W 67.50' 12" Oak (nail)



igned by

Stephen V. Vallier

Date

12/15/95

urveyor's Michigan License No.

28428