

**SURVEY & REMONUMENTATION**

MAR 21 1997

LIBEP 1951 PAGE 689

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECORDS & DEEDS  
11811

**COMMISSION**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

1996 DEC 23 PM 3:51

For corners in

Muskegon  
(County)

Located In:

Corner Code =#

1. Public Land Survey	T	<u>11</u> N	R	<u>17</u> W	<u>E 12</u>
	T	___	R	___	___
	T	___	R	___	___
	T	___	R	___	___
2. Property Controlling in Section	S	___	T	___	R
	S	___	T	___	R
3. Miscellaneous Property in Sec.	S	___	T	___	R
	S	___	T	___	R

*Carroll*  
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Ralph W VanRiper, in a field survey on Nov. 29, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1/4 Corner between Sections 32 and 33, T 11 N, R 17 W, Fruitland Township  
Post set by GLO Surveyors in 1837 (W Oak 6", S 34° E, 27 L) ( W Oak 7", N 16° W, 14 L)

MCRC 1950's Witness Sheets : 1/2" Gas Pipe with 2 Witnesses  
MCRC Current Witness Book : RR Spike with 7 Witnesses

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found RR Spike over 1/2" Pipe over 3/4" Pipe, in Asphalt pavement of Orshal Rd.  
Verified location with existing witnesses

*June 4, 1996 sv*  
PORTION OF SAID RECORDED CORNER REVISITED & RATIFIED BY MUSKEGON COUNTY AFTER ORIGIN BY APPEARANCE WITH P.A. 645, OF 1980

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" Cast Iron Monument with County Survey Cap, in Asphalt pavement  
N 80° E 43.68' Found Spike in N side of 20" Oak  
East 51.06' Found Spike in S side of Power Pole  
S 45° E 42.53' Set Spike in S side of 10" Oak  
S 40° W 58.40' Set Spike in S side of 12" Oak  
S 80° W 42.72' Found Spike in N side of 16" Oak  
N 35° W 43.08' Set Spike in S side of 10" Oak



Signed by Ralph W. Van Riper Date 12/20/96  
Surveyor's Michigan License No. 16948

LIBEP 1951 PAGE 689

11811