

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 REGISTER OF DEEDS
 APR 28 1995
 1995 03 19

For corners in Muskegon County

Located in: Corner Code #

1. Public Land Survey T 11N R 17W G-5
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____
 3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____
 5. Private Claims _____

SURVEY & REMONUMENTATION

APR 28 1995

COMMISSION

Register of Deeds Stamp & File Number

I, Donald G. Sandel, in a field survey on Nov. 11, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (1) GLO: To Beech, 6" corner sections 9, 10, 15, 16 on July 2, 1837. Witness: Maple 20" N41°E 0.18 chains.
 - (2) MCRC (1950's); rail road spike; witnesses: NW 79.25' (UNK OBJ.), SW 42.08' Black Gum.
 - (3) Found 1 1/2" pipe ±3' North of center line "X" as recorded by Francis Smith (A-118) on October 16, 1980; witnesses: N50°E center line 2" Spruce 54.2'; S 42°E center line Telephone Box 53.8', S15°E set nail W side 10" W Pine 97.32', N46°W set nail NE side Power Pole 78.44'.
 - (4) Corner destroyed in the construction of road. Set monument box with 1/2" rod, as recorded by John Lazarock on Jan. 10, 1990, Liber 1503, Page 600. Witnesses: N36°W 78.47' Power Pole, N20°E 162.86' 16" Maple, N38°E 88.17' 4" Spruce, S10°E 97.25' 10" Pine.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (1) Found 1/2" rod in 1 1/2" well point pipe in county monument box (w/cover) ±3' N of center line Michillinda Road and at approximate center line of Simonelli Road. Verified corner location using existing PK's in asphalt and witness in NW Quadrant.
 - (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by the Muskegon County Peer Group, April 5, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" D Cast Iron "County Survey" monument in place of found 1/2" rod and well point; witnessed as follows:

- N46°W, found nail NE side, Power Pole, 78.44'
- N44°W, set nail SW side, Light Pole, 46.60'
- N30°E, set N. end of curb, back of curb, 46.80'
- S23°E, set nail W side, W. Pine, 69.90'
- S14°E, set nail NE side, W. Pine, 86.86'
- S65°W, set W. end of curb, back of curb, 50.05'

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

APR 5 1994

25870

PROFESSIONAL SURVEYOR

Signed by Donald G. Sandel
Surveyor's Michigan License No. 25870

Date 16 December 1994