

**SURVEY & MONUMENTATION**

*L1871 Pg. 635*

**A1746**

**APR 04 1996**

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in  
**COMMISSION**  
**Muskegon**  
(County)

	Located In:	Corner Code #
1. Public Land Survey	T <u>11N</u> R <u>17W</u>	<u>G-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
REGISTER OF DEEDS

1995 FEB 18 PM 4:17

Register of Deeds Stamp & File Number

I, Stephen V. Vallier, P.S., in a field survey on November 6, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K
2	6	5	4	3	2					
3										
4	7	8	9	10	11					
5										
6	18	17	16	15	14					
7										
8	19	20	21	22	23					
9										
10	30	29	28	27	26					
11										
12	31	32	33	34	35					

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**


- A. Description of original monument and accessories and/or subsequent restoration:
- 1837 GLO set corner N 30 deg. W 31 Links 9" White Oak  
S 12 deg. E 32 Links 24" Pine
  - 1950's MCRC - 1" Iron
  - 1981 R. VanRiper found 3/4" Iron Pipe recorded LCRC Liber 1230 Page 367  
E 71.92' 20" Oak  
NNE 57.65' 14" Oak  
SSW 28.50' 8" Pine

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- Found 4" x 30" Cast Iron Monument with County Survey Cap. Checks witnesses of LCRC Liber 1478 Page 509

POSITION OF SAID RECORDED CORNER REVIEWED & RATIFIED BY MUSKEGON COUNTY PEER GROUP IN ACCORDANCE WITH P.A. 345, OF 1990

*Nov 13, 1995*

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Found 4" x 30" Cast Iron Monument with County Survey Cap.
- N 35 deg. E 45.72' 8" Pine (nail with blaze)
  - S 83 deg. E 71.96' 20" Oak (nail with blaze)
  - S 10 deg. E 43.60' 12" Twin Oak (nail)
  - S 28 deg. W 28.45' 6" Pine (nail with blaze)
  - N 80 deg. W 34.50' 6" Oak (nail with blaze)
  - N 58 deg. W 16.02' 6" Oak (nail with blaze)
  - East 33.00' 1/2" Iron Rod



Signed by Stephen V. Vallier Date 12/15/95  
Surveyor's Michigan License No. 28428