

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Muskegon County Located in: Corner Code #

- 1. Public Land Survey T 11N R 17W G-13
- T _____ R _____
- T _____ R _____
- T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
- in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
- Property in Sec. S _____ T _____ R _____
- 4. Lot No _____, Recorded Plat _____
- 5. Private Claims _____

SURVEY & REMONUMENTATION

APR 28 1995

Register of Deeds Stamp & File Number

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 REGISTRY OF DEEDS
 APR 29 PM 3:20

I, Donald G. Sandel, in a field survey on Nov. 30, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (1) GLO: Set post corner of sections 33 and 34, December 31, 1836.
Aspen 10" N36°W 0.21 chains
Aspen 10" N21°E 0.92 chains
- (2) MCRC (1950's) witnesses: NE 45.3 6" J. Pine
SE 41.6 T.P.
SW (UNK DIST.) 6" J. Pine
- (3) April, 1952 M.M. Buck Survey: NE 46.1' 4" J. Pine, SE 46.75' T. Pole, SW 59.8' 4" J. Pine.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1) Found 1" Pipe 5.9' N of center line River Road.
- (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by the Muskegon County Peer Group, April 5, 1994.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" D Cast Iron "County Survey" monument in place of found 1" Pipe; witnessed as follows:
 N63°E, set nail NW side, 13" Pine, 62.63'
 S37°E, set nail NE side, 25" Maple, 49.71'
 South, found nail E side, Power Pole, 35.93'
 S23°W, found nail E side, Power Pole, 82.02'
 S45°W, set nail E side, 16" Pine, 59.24'
 N28°W, found nail E side, Power Pole, 58.37'

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

Apr 5, 1994

Signed by Donald G. Sandel Date 16 December 1994
 Surveyor's Michigan License No. 25870

