

1993

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1993 DEC 29 PM 12: 57

Carrie Carter
REGISTER OF DEEDS

For corners in

Muskegon
(County)

Located In:

Corner Code #/

- 1. Public Land Survey T 11N R 17W I-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat
- 5. Private Claims _____

Register of Deeds Stamp & File Number

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|---|----|---|----|---|----|---|----|---|----|---|---|
| 2 | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | | 17 | | 16 | | 15 | ● | 14 | | 13 | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | | |
| 13 | | | | | | | | | | | | | |

I, Donald G. Sandel, in a field survey on July 21, 1993, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (1) GLO set quarter section post June 30, 1837
Hemlock 6" S30°W 0.11 ch
Beech 9" N59°E 0.10 ch
- (2) MCRC (1950's) I.P. witnesses: SW 94.70' T. Hall; SE 121.85 12" Pine
- (3) Muskegon County witness book witnesses: Iron.
NW 49.43' P.P.; ESE 71.55' 8" Pine; SSE 135.12' Tri 12" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1) Found 1/2" pinch pipe in asphalt at intersection of Weber & Tood Roads. Below 1/2" pipe was 1 1/2" x ±3' pipe.
- (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by Muskegon County Peer Group, July 7, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 20" cast iron "County Survey" monument in place of found 1/2" pinch pipe; witnessed as follows:
 S 60°E, found, nail N. side, 17" White Pine, 71.60'
 N 61°E, found, S. side of post, stop sign pole, 44.49'
 N 38°W, set, 4" nail on SW side with County tag, power pole, 49.46'
 N 43°W, set, 4" nail on S. side with County tag, 8" White Pine, 100.18'
 S 70°W, found, N. side of post, stop sign, 45.54'
 S 28°E, set, 4" nail on W. side, 12" White Pine, 101.53'

Signed by Donald G. Sandel

Date 29 December 1993

Surveyor's Michigan License No. 25870