

COMMISSION LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

Carrie Carter
REGISTER OF DEEDS

For corners in

Muskegon <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T 11N R 17W	I-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, Donald G. Sandel, in a field survey on July 27, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (1) GLO set post corner sections 14, 15, 22, 23; June 30, 1837.
Hemlock 16" N76 deg. E .13 ch
Beech 8" S77 deg. W .34 ch
- (2) MCRC (1950's): I.P. NW 77.6' 7" A; SW 61.25' 24" M; SE 52.25' 10" M
- (3) Muskegon Co. witness book witnesses: Iron P. NW 77.6' 7" apple; SW 61.25' 24" Maple; SE 52.25' 10" Maple

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1) Found 2" x 2.7' iron pipe at "T" intersection of Weber and Riley Thompson Roads (both paved). Varified corner location using available witnesses and evidence.
- (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by Muskegon County Peer Group, July 7, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 4" x 20" cast iron "County Survey" monument in place of found 2" iron pipe; witnessed as follows:

- S 70 deg. E, found, rail-road spike on W side, 24" Maple, 30.33'
- S 32 deg. E, found, nail on W side, 28" Maple, 51.77'
- S 37 deg. W, found, nail on SE side, 26" Maple in yard, 61.31'
- S 65 deg. W, found, N edge of pole, stop sign, 44.20'
- N 48 deg. W, set, 3 1/2" nail on NE side, 7" Twin Walnut, 58.21'
- N 40 deg. W, found, nail on W side, 10" Apple, 77.78'

Signed by Donald G. Sandel Date 29 December 1993

Surveyor's Michigan License No. 25870