

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 REGISTER OF DEEDS
 APR 28 1995
 11:32 AM

Located in: _____ Corner Code # _____

1. Public Land Survey T 11N R 17W
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

I-10 SURVEY & A1512
 REMONUMENTATION
 APR 28 1995
 COMMISSION

Register of Deeds Stamp & File Number

I, Donald G. Sandel, in a field survey on Nov. 15, 1994 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
- (1) GLO: To Hemlock, 16" for quarter section corner June 30, 1837.
 - (2) MCRC(1950's) Iron Pipe; Witnesses: E 69.7' SW corner barn.
 - (3) Found 1" Iron Pipe as recorded by Francis F. Smith on December 23, 1971 L976, P775. Witnesses: Spike in 10" Pine Tree W 36.30', Spike in 24" Maple Tree NE 60.00', Spike in 14" Twin Apple Tree E. 29.50'
- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
- (1) Found 1" X 2' Iron Pipe in asphalt approximately 1' West of center line Weber Road. Verified corner location with existing witness.
 - (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by the Muskegon County Peer Group, April 5, 1994.
- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
- Set 4"D Cast Iron "County Survey" monument in place of found 1" iron pipe; witnessed as follows:
- S72°W, set nail S side, 10" Jack Pine, 68.06'
 - S85°W, set Nail N side of 10" Jack Pine, 39.55'
 - N50°W, found nail NE side, 8" Jack Pine, 52.76'
 - N25°E, found nail W side, 22" Maple, 72.57'
 - S35°E, set nail SW side, 9" Jack Pine, 42.98'
 - S30°E, found nail SW side, 9"/12" Twin Red Pine, 53.55'

POSITION OF SAID
 RECORDED CORNER
 REVIEWED & RATIFIED
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1930

Apr 5, 1994 sw

Signed by Donald G. Sandel Date 16 December 1994
 Surveyor's Michigan License No. 25870

