

1993

1744 230

1993 DEC 29 PM 12:58

COMMISSION

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 11N R 17W J-6
T _____ R _____
T _____ R _____
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S T R
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____
- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Carrie Carter
REGISTER OF DEEDS

Register of Deeds Stamp & File Number

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Donald G. Sandel July 19 93

I, _____, in a field survey on _____, 19____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- (1) Corner not set by GLO Survey.
- (2) No MCRC witnesses on records for this corner (1950).
- (3) Witnesses from Muskegon Co. witness book
N 76.07' quad tree NE 76.07' cluster W.D.V

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- (1) Found inverted 2 1/4" X 11 1/4" pinched pipe on sand-gravel Rd (Todd)
- (2) Historical usage, documentation, and evidence of corner location reviewed and ratified by muskegon county peer group, July 3, 1993.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4 x 20" cast iron "County Survey" monument in monument box in place of found pipe; witnessed as follows:
N 52°E, Found, nail SE trunk of Quad tree, 53.46'
N 14°E, set, nail E side, 8" Maple, 63.17'
S 82°W, set, nail N side, 10" Maple, 79.82'
S 72°W, set, nail N side, 7" Elm, 48.39'
S 02°E, set, nail W side, 6" Popular 54.89'
S 55°E, set, nail SE side 10" Oak 76.13'

Signed by Donald G. Sandel

Date 28 December 1993

Surveyor's Michigan License No. 25870