

**SURVEY & REMONUMENTATION**

LIBER 1952 PAGE 812

STATE OF MICHIGAN  
COUNTY OF MUSKEGON  
RECEIVED FOR RECORD

MAR 21 1997

**LAND CORNER RECORDATION CERTIFICATE**

1996 DEC 30 AM 8:48

For corners in  
Muskegon  
(County)

**COMMISSION**

Filing Requirement of Act 74, Mich. P.A. 1970

*Carrie Carter*  
REGISTER OF DEEDS

A1842

Register of Deeds Stamp & File Number

	Located In:	Corner Code #
1. Public Land Survey.	T 11N R 17W	K-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, Stanley H. Shackelford, P.S. in a field survey on OCTOBER 30, 19 96, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

- A. Description of original monument and accessories and/or subsequent restoration:
- 1837 G.L.O. 8 INCH HEMLOCK AT CORNER NO WITNESSES
  - 1889 MUSKEGON COUNTY RECORDS PAGES 40 AND 41  
TOWN LINE JOG OF 16.06 CHAINS AND TIE NORTH OF 40.84 CHAINS
  - 1950's NO CORNER DESCRIPTION NORTHWEST 46.70'  
TOWN LINE JOG 1081.5 NORTHEAST 78.08'

CORNER FENCE POST  
POWER POLE

SEE ATTACHED EXHIBIT "K-13"

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN MONUMENT BOX

NORTH 40° EAST	79.95'	POWER POLE
NORTH 55° WEST	109.50'	POWER POLE
SOUTH 55° EAST	64.70'	POWER POLE

CHECKS MILE MEASURE NORTH WITHIN 2 FOOT ± FROM 1889


POSITION OF SAID  
RECORDED CORNER  
REVIEWED & RATIFIED  
BY MUSKEGON COUNTY  
PEER GROUP IN ACCORDANCE  
WITH P.A. 345, OF 1990

9/10/90

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

FOUND CAST IRON MONUMENT WITH COUNTY SURVEYOR LEGEND IN MONUMENT BOX

NORTH 40° EAST	79.95'	POWER POLE FOUND SPIKE
NORTH 55° WEST	109.50'	POWER POLE FOUND SPIKE
SOUTH 55° EAST	64.70'	POWER POLE FOUND SPIKE



Signed by Stanley H. Shackelford Date 12-26-96  
Surveyor's Michigan License No. 30100

A1842

LIBER 1952 PAGE 812

EXHIBIT K-13

LIBER 1952 PAGE 813

1974 LIBER 1036, PAGE 232 BY F. SMITH  
FOUND 1/2-INCH ROD

NORTHEAST	78.00'	POWER POLE
SOUTHEAST	64.70'	TELEPHONE POLE
NORTHWEST	109.60'	TELEPHONE POLE

1983 LIBER 1258, PAGE 271 BY C.F.L.

FOUND 1/2-INCH ROD ON TOP OF 1-INCH PIPE IN MONUMENT BOX  
CHECKS WITH WITNESSES LIBER 1036, PAGE 232

NORTH 40° EAST	79.95'	POWER POLE
SOUTH 55° EAST	64.70'	POWER POLE
NORTH 55° WEST	109.50'	POWER POLE