

1994 DEC 29 AM 10:15

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Muskegon
(County)

Located In:

Corner Code 77

Carrie Carter
REGISTER OF DEEDS

- 1. Public Land Survey T 11 R 17 1-9
T _____ R _____ SURVEY &
T _____ R _____ REMONUMENTATION
T _____ R _____
- 2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____ APR 28 1995
- 3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____ COMMISSION

A1621

Register of Deeds Stamp & File Number

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

I, Stephen V. Vallier field survey on December, 1994
do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

- 1837 GLO set corner
- 1950's M.C.R.C. Tie Map - witnesses only
- 1983 C.F. Lewandowski - L.C.R.C. Liber 1260 Page 165 - found 1/2" iron rod on top of 3/4" solid iron. Reset with 4" x 30" cast iron monument with County survey Cap.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 4" cast iron monument with County Survey Cap.
Accepted position of corner due to evidence of Historical usage and consistent documentation.

POSITION OF SAID
RECORDED CORNER
REVIEWED & RATIFIED
BY MUSKEGON COUNTY
PEER GROUP IN ACCORDANCE
WITH P.A. 345, OF 1990

Dec 14, 1993

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

4" Cast Iron monument with County Survey Cap.

- S 25 deg W 70.45' 18" Maple with nail
- S 50 deg E 55.00' 16" Maple with nail
- N 45 deg E 44.80' 14" Maple with nail
- N 55 deg W 80.75' 14" Maple with nail



Signed by *Stephen Vallier*

Date *Dec 27, 1994*

Surveyor's Michigan License No. 28428