

LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF MUSKEGON
 RECEIVED FOR RECORD

200 DEC 20 PM 1: 52

For corners in Muskegon County Located in: Corner Code #

1. Public Land Survey T 12N R 17W E-7
 T _____ R _____

T _____ R _____

SURVEY & REMONUMENTATION

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____ **JAN 31 2001**

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____ **SECTION**

4. Lot No _____, Recorded Plat _____

5. Private Claims _____

Mark Fairchild
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, Donald G. Sandel, in a field survey on July 10, 2000 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

POSITION OF SAID *Ratified*
 RECORDED CORNER *sw*
 REVIEWED & RATIFIED *5/2/00*
 BY MUSKEGON COUNTY
 PEER GROUP IN ACCORDANCE
 WITH P.A. 345, OF 1990

A. Description of original monument and accessories and/or subsequent restoration:

- GLO: Set Post Corner, April 1, 1838: Beech 10° S05°E .44 chains, Beech 8° N80°W .40 chains.
- Muskegon County Road Commission, Railroad Spike: SE 53.31' Fence Post, NNE 56.90' Telephone Pole, SE 52.65' Fence Post, NW 88.0' 12" Apple, NE 52.65' Power Pole, NNW 35.38' 20" Elm, SW 43.60' Telephone Cable Marker, SSE 73.62' Telephone Pole.
- D.G. Sandel #25870 on March 23, 1995 found Railroad Spike: N31°E Power Pole 56.70', N53°E Power Pole 52.63', S58°W Fence Post 52.86', S17°E Power Pole 75.29'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- Found Railroad Spike in Monument Box at intersection of Sikkenga Road (N/S Asphalt) and Eilers Road (gravel to West, two-track to East).
- Historical usage, documentation, and evidence of corner location reviewed and ratified by the Muskegon County Peer Group, May 2, 2000.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 2 3/4" x 31" Cast Iron "County Survey" Monument stamped #25870 in place of found Railroad Spike; witnessed as follows:

- N32°E, found P.K. Nail W side, Utility Pole, 56.70'
- N55°E, set Nail NW side, Utility Pole, 51.94'
- S57°E, found Nail S side, wooden Fence Post, 52.86'
- S16°E, found P.K. Nail W side, Utility Pole, 75.29'
- S74°W, set N edge of Post, Stop Sign, 46.20'
- N39°W, set center of Post, Street Name Sign, 48.35'

Signed by Donald G. Sandel
 Surveyor's Michigan License No. 25870

Date 15 December 2000



A2146