

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 42 N.R. 25 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 4 and 5

CORNER MONUMENT One-inch galvanized pipe with four-inch brass cap

DATE MONUMENT PLACED AND WITNESSED June 16, 1961

WITNESSES TO CORNER..... Cedar 12" N26W 23.5 links



Cedar 7" S84E 35 links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from one original cedar bearing tree on which the lower face showed the "BT" scribe marks very plainly. The other bearing tree was completely rotted, except for roots in the ground indicating that a cedar tree once occupied the spot. Squared post had been set in proper location.

SURVEYOR'S SEAL

SIGNED Anne A. M. Stea DATE 6/20/61
REGISTERED LAND SURVEYOR