

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42 N.R. 25 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 21 and 28

CORNER MONUMENT One-inch galvanized pipe with four-inch aluminum cap

DATE MONUMENT PLACED AND WITNESSED April 10, 1962

WITNESSES TO CORNER..... Cedar 5 N 76 E 29 Links



Tamarack 4 N 40 E 29.5 Links

Spruce 6 S 72 W 35.5 Links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. Corner was set from the two original tamarack bearing trees. The one to the SW was a dead tree 30 feet high with both faces plain, the upper face showing distinct scribe marks. The other tamarack was just a weathered stub, one foot high, with faces completely weathered away. The bearings and distances checked with original field notes. No post was found, but found the pointed stub of the original post 18 inches long, also stub of another post, perfectly preserved by the water in the swamp, in the proper location.

SURVEYOR'S SEAL

SIGNED Orme A. Metan DATE 4/11/62  
REGISTERED LAND SURVEYOR