

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY  
43  
T 42 N R 25 W

DESCRIPTION OF CORNER Section corner for sections  $\frac{31}{32}$  T43N R25W  
 $\frac{6}{5}$  T42N R25W

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/27/69, F. J. Bray with B. McDonald

WITNESSES TO CORNER..... 10" Elm (S.32) (NBT) N 81° E, 38 $\frac{1}{2}$  links



7" H. Maple (S.6) (NBT) S 50 W, 59 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between section corners two miles to north, one mile to west, and 1/4 corners 1/2 mile to east and to south. No original evidence found.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

9/25/69

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68