

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 42 N.R. 25 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 corner for sections 6/5

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 8/5/69, F. J. Bray

WITNESSES TO CORNER..... 8" Cedar (1/4 S) (NBT) N 80° W, 07½ links



7" Cedar (1/4 S) (NBT) N 84° E, 23 links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

this corner was replaced from original BT (18" Tamarack S 71° E, 22 links)  
which is down rotted stub with axe marks and overgrowth of upper face. Rotted  
wood in place of cedar B.T. to NW.

SURVEYOR'S SEAL

SIGNED Frank J. Bray DATE 10/6/69  
REGISTERED LAND SURVEYOR  
Frank J. Bray