

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY  
T 43 N R 24 W

DESCRIPTION OF CORNER Meander corner for sections 30/29

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9/8/69, F. J. Bray

WITNESSES TO CORNER..... 9" Cedar (M.C.) (NBT) N 21° W, 23½ links



6" Elm (M.C.) (NBT) N 77° E, 11½ links

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was replaced from two possible B.T. stumps. Cedar to NW burned badly, no marks visible. Cedar to NE was buried. Both stumps check well for bearings and distances. Corner lies on west bank of stream as recorded in original field notes. Section corner in river 62.3 links south of meander corner.

SURVEYOR'S SEAL

DISTRIBUTION:

SIGNED

*Frank J. Bray*  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

10/2/69

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68