

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43. NR. 24 W. . .

Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 28, 33

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 1/4" brass cap

WITNESSES TO CORNER 10" Cedar S 81° W 45 links

"1/4" S NBT"

8" Hard Maple N 60° E 48 links

"1/4" S NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced 1/4 Corner from two original B.T.s.

Y. Birch N 3° W 31 links in poor condition, cut down.

Cedar stump South 9 links, trace of overgrowth. No scribe mark.

Corner found by Arne Metsa, District Forester and Art Enger, Ass't Forester.

Squared and scribed 6" E 1m at Corner.

There is a blazed line south about 4 chains to winter road.

Corner placed and witnessed 2-1-57.

SURVEYORS SEAL

SIGNED

*Billy D. Buckler*  
REGISTERED LAND SURVEYOR

DATE 2-7-57