

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43. NR. 24 W. . .

Marquette

COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 19, 20, 29, 30

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap

WITNESSES TO CORNER

| | | |
|-----------------|-------------------|------------------|
| <u>7" Cedar</u> | <u>N 26° W</u> | <u>31 links</u> |
| | <u>"S 19 NBT"</u> | |
| <u>5" Cedar</u> | <u>N 62° E</u> | <u>22½ links</u> |
| | <u>"S 20 NBT"</u> | |

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Corner from one Tamarack B.T. bear N 75° W 30 links in good condition. Scribe marks "BT" still plain.

Found Cedar Post in place as set by Arne Metsa, District Forester.

Squared and scribed 5" Cedar Tree at Corner.

Corner shown to us by Art Enger, Ass't Forester.

Placed location poster on old winter road 1/2 chain East of Corner.

Corner placed and witnessed 2-1-57.

SURVEYORS SEAL

SIGNED

Billy D. Buckler
REGISTERED LAND SURVEYOR

DATE 2-7-57