

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 24 W


Marquette COUNTY

DESCRIPTION OF CORNER 1/4 Corner Between Sections 8 and 17

CORNER MONUMENT 1 Inch galvanized pipe with 4 inch brass cap.

DATE MONUMENT PLACED AND WITNESSED May 9, 1961

WITNESSES TO CORNER.....



Cedar 10" N 62 E 76 Links

Hemlock 12" S 88 W 10 Links

AND

Yellow Birch 10" S 32 E 59.5 Links

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was set from two original BT's. Spruce BT was a sawed stump, rotten; but peeling off the decayed overgrowth revealed the lower face with faint scribe marks evident. The overgrowth showed definite scribe marks. The yellow birch BT showed no scribe marks or face as the stump was almost completely rotted except for a few hard slabs 12 to 18 inches high remaining. It was definitely the remains of a large yellow birch stump. The stumps fit the field notes in size, species, bearings, and distances. This corner was located by A. Metsa on April 28, 1961.

SURVEYOR'S SEAL

SIGNED

A. Metsa
REGISTERED LAND SURVEYOR

DATE

5/10/61