

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 24 W


Marquette COUNTY

DESCRIPTION OF CORNER Section corner common to Sections 7, 8, 17 and 18

CORNER MONUMENT 1 inch galvanized pipe with 4 inch brass cap

DATE MONUMENT PLACED AND WITNESSED May 3, 1961

WITNESSES TO CORNER..... Hemlock 7" S 57 W 39 Links



Cedar 7" N 84 E 42.5 Links

White Spruce 8" S 31 E 33 Links

AND

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set from the stumps of two original ^{birch} bearing trees. Both stumps were rotten but one stump showed the face when the rotted overgrowth was removed. The notch showed on the overgrowth but no scribe marks on either the overgrowth or the face. The other stump had been sawed at the notch. Stumps fit the original notes in species, size, bearing, and distance. An old squared post was found in proper location. Two old cedar trees had been faced in the direction of corner. On one the writing was illegible but the other dated May, 1925 had the names of two timber cruisers and the proper section corner designation. Blazed lines run North, South and East from this corner. Corner checks with swamp edge to West.

This corner placed and witnessed by A. Metsa and W. Oliver.

SURVEYOR'S SEAL

SIGNED

A. Metsa
REGISTERED LAND SURVEYOR

DATE

5/5/61