

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. S., R. <u>24, 25</u> W.	<u>A-2, D-3</u>
2. PROPERTY CONTROLLING IN SECTION <u>6</u>	, T. <u>43</u> N. S., R. <u>24, 25</u> W.	<u>3</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, **Frank J. Gray** do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 23 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. ~~Description~~ Description of original monument and accessories and/or subsequent restoration:

A-2	Spruce	5	N050 ^g	27 links		D-3	Hemlock	9	N49 ^g E	21 links
	Spruce	5	N29 ^g W	11 links			Maple	8	S38 ^g W	14 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- A-2** This corner was set mid-point and on a line between section corners north and south.
- D-3** This corner was set mid-point and on a line between section corners east and west.
- 3** This corner was set mid-point and on a line between corner south and town corner north.

C. Description of monument and accessories established by and position of the corner:
A-2 1" pipe with 1" brass cap. **D-3** 1" pipe with 1" aluminum cap.
3 1 1/2" pipe All bearings are magnetic.

A-2	12" Cedar (1/8) (NBT)	N27 ^g E	8.1'
	10" Cedar (1/8) (NBT)	S51 ^g E	12.0'
D-3	4" B. Spruce (1/8) (NBT)	N25 ^g E	21.1'
	12" Y. Birch (1/8) (NBT)	S31 ^g W	16.2'
3	1" Cedar (N 1/16) (BT)	S60 ^g E	8.6'
	5" Cedar (N 1/16) (BT)	S53 ^g W	3.0'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Frank J. Gray DATE July 3, 1973
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

13575

SURVEYOR'S MICHIGAN REGISTRATION NO. _____