

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette County

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>43</u> N. R. <u>24</u> W.	<u>E-4, E-5</u>
2. PROPERTY CONTROLLING IN SECTION <u>9</u>	T. <u>43</u> N. R. <u>24</u> W.	<u>10</u>
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 25 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Woodpost:

E-4	Tamarack	12	S40°W	12 links
	Tamarack	6	N70°E	21 links
E-5	Spruce	10	S70°E	23 links
	Tamarack	11	S58°W	28 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- E-4** This corner was set mid-point and on a line between section corners north and south. Corner lies on east edge of old North and South winter road.
- E-5** This corner was re-established with measurements to swamp edges to west and south, stream to east checks fairly well. Its course may have changed due to winter road.
- 10** This corner was set mid-point and on a line between section corner south and corner north. Corner lies on east edge of old winter road.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

All 1" iron pipe with 4" aluminum cap. All bearings are magnetic.

E-4	8" Cedar (1/8) (NBT)	S41°W	26.5'
	4" Cedar (1/8) (NBT)	S86°E	7.2'
E-5	12" Cedar (817) (NBT)	S59°W	31.6'
	9" W. Pine (817) (NBT)	S89°W	35.3'
	6" Balsam (816) (NBT)	S19°E	4.7'
10	12" Cedar (8 1/16) (BT)	S38°W	25.1'
	9" Cedar (8 1/16) (BT)	N79°W	12.6'

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE July 3, 1973

APPROVED AND SIGNED BY Frank J. Bray MICHIGAN REGISTERED LAND SURVEYOR DATE _____ (SEAL)

13575