

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

Marquette County

| FOR CORNERS OF --:                         | LOCATED IN--:  | CORNER CODE NUMBER |
|--|--|--------------------|
| 1. PUBLIC LAND SURVEY _____                | T. <u>43, 44<sup>N</sup></u> S., R. <u>24</u> <u>SE</u> W. | A-1, B-1           |
| 2. PROPERTY CONTROLLING IN SECTION _____   | T. <u>43, 44<sup>N</sup></u> S., R. <u>24</u> <u>E</u> W.  | 1                  |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | T. _____ S., R. _____ E. W.                                |                    |
| 4. LOT NO. _____, RECORDED PLAT _____      |  |                    |
| 5. PRIVATE CLAIMS _____                    |  |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 21 1973, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**Woodpost:**

|     |                                       |    |       |          |
|-----|---------------------------------------|----|-------|----------|
| A-1 | Fir                                   | 10 | N24°E | 39 links |
|     | Sugar                                 | 8  | S34°W | 35 links |
|     | Subsequent monument: Squared woodpost |    |       |          |
|     |                                       |    |       |          |
| B-1 | Sugar                                 | 6  | N23°E | 9 links  |
|     | Ignon                                 | 12 | N59°W | 18 links |

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

**A-1 This corner was set at old squared woodpost which checks well with other corners in the area.**

**B-1 This corner was set by single proportionate measurement between town corner west and section corner east.**

**1 This corner was set by single proportionate measurement between town corner west and 1/2 corner east.**

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

|   |   |
|---|---|
| A-1 1" pipe with aluminum cap (1/2")    | B-1 1" pipe with 1/2" brass cap.                    |
| 1 1" pipe                               | <u>All bearings are magnetic.</u>                   |
|   |   |
| A-1 4" H. Maple (81) (NBT) S52°W 9.9'   | B-1 9" Cedar (1/2") (NBT) S58°W 31.9'               |
| 4" Y. Birch (836) (NBT) N43°W 37.7'     | 16" Basswood (1/2") (NBT) N61°W 47.7'               |
| 9" Balsam (831) (NBT) N26°E 23.0'       |   |
| 18" Elm (NBT) S70°E 11.0'               |   |
|   |   |
| 1 6" H. Maple (W 1/16) (BT) S86°E 11.8' | Dead 10" Balsam NW 2.0' squared & scribed for post. |
| 6" H. Maple (W 1/16) (BT) S42°W 15.8'   |   |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray DATE July 3, 1973  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575