

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD


Marquette COUNTY  
43  
T 43 N R 25 W

DESCRIPTION OF CORNER 1/4 Corner between Sections 25 and 26

CORNER MONUMENT One-inch galvanized pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED November 20, 1969

WITNESSES TO CORNER..... Cedar 10" N48°E 49.0 links



Cedar 12" S20°E 5.5 links

Cedar 6" S68°W 19.5 links

AND  
Cedar 6" N9°W 24.8 links

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Corner was set from original tamarack BT's. Tamarack 10 S61E 18 link was a short dead rotted stub. By breaking off slab off of almost completely overgrown face the "B.T." scribe marks were exposed. They showed exceptionally plain. The other original tamarack, N52W 13 links, was an old, down, rotted tree, broken off at almost ground level. Stump was badly rotted and crumbled. The stump fitted perfectly in bearing and distance. Corner was set by Arne Metsa and Carl Brousseau.

SURVEYOR'S SEAL

SIGNED

Arne Metsa  
REGISTERED LAND SURVEYOR

DATE November 26, 1969

DISTRIBUTION:

County Courthouse  
Area Forester (Regions I & II)  
District or Region Surveyor  
Forestry Div., Lansing

R 4047  
Rev. 10/68