

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code #

- | | | |
|------------------------------------|---------------------------|--------------------------|
| 1. Public Land Survey | T <u>43N</u> R <u>25W</u> | <u>E-12, D-11, D-13.</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	15		17		18		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David B. Babbitt, in a field survey on 5/5/88, 19_____, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-12. East 1/4 corner of Section 32. Mich. DNR 9/3/69 F. Bray, Set 1" pipe with 4" aluminum cap in dry pond bed. 6" dead cedar, S58W, 77½ Lks. 4" leaning cedar, N72E, 38½ Lks.

D-11. North 1/4 corner of Section 32. Mich. DNR 9/25/69, F. Bray. Set 1" pipe with 4" aluminum cap. 7" h.maple, N31E; 10½ Lks. 12" h.maple, N62W, 53 Lks.

D-13. South 1/4 corner of Section 32. Mich. DNR 9/25/69. 1" pipe w/4" aluminum cap set from original bearing trees. 10" cedar, N11E, 14½ Lks. 7" tamarack, S72W, 28½ Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-12. Found 1" pipe with 4" aluminum cap in pond about 1' deep. Both of F. Bray's 1969 NBT's are in place but the SW dead cedar is now partially blown down and is leaning into the tops of other trees. Marked three new NBT's.

D-11. Found 1" pipe with 4" aluminum cap. Both of F. Bray's 1969 NBT's are in place alive and standing. Marked two new NBT's.

D-13. Found 1" pipe with 4" aluminum cap. Both of F. Bray's 1969 NBT's are in place in good condition. Also found parts of cedar blown down in place, showing partially healed over blazes, for the NE original bearing tree. Marked two new NBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-12. DNR Monument
 5" spruce, N19E, 91.3'
 5" leaning cedar, N72E, 25.2' (F. Bray)
 6" dead cedar, S61W, 51.0' ← NBTs
 6" spruce, S60W, 94.4'
 4" balsam, N85W, 93.2'

D-11. DNR Monument
 15" h.maple, N59W, 35.1' (F. Bray
 11" h.maple, N35E, 7.0' ← NBTs)
 11" cedar, N19E, 95.1'
 4" spruce, S37W, 23.05'

D-13. DNR Monument
 11" cedar, N14E, 9.4' Bray
 7" tamarack, S76W, ← NBTs)
 18.9'
 5" tamarack, S38W, 24.0'
 5" cedar, S79E, 9.1'

Signed by David B. Babbitt

Date 8-1-88

Surveyor's Michigan License No. 21558