

**LAND CORNER RECORDATION CERTIFICATE**  
**Filing Requirement of Act 74, Mich. P.A. 1970**

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code #
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S <u>32</u> T <u>43N</u> R <u>25W</u>	<u>10, 3.</u>
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, David B. Babbitt, in a field survey on 5/4, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

A. Description of original monument and accessories and/or subsequent restoration:

10. S1/16 cor. on the west sec. line of Section 32. Mich. DNR 9-2-69, F. Bray, Set 1" pipe with 4" aluminum cap. 9" balsam, N36E, 10 Lks. 24" w.pine, S23E, 28½ Lks.

3. N1/16 cor. on the west sec. line of Section 32. Mich. DNR 9-4-69, set 1" pipe w/4" aluminum cap. 7" h.maple, N53E, 13 Lks., 7" y.birch, S55W, 06 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

10. Found 1" pipe with 4" aluminum cap. Both of F. Bray's 1969 BT's are in place alive and well. Marked two new BT's.

3. Found 1" pipe with 4" aluminum cap. Both of F. Bray's NBT's are in place but the yellow birch is dead and down. Marked 3 new NBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

10. DNR Monument  
 5" spruce, S88W, 54.0'  
 6" balsam, N31W, 29.8'

3. DNR Monument  
 8" h.maple, N58E, 8.8'←(F.Bray NBT)  
 7" " , S61E, 19.6'  
 6" " , N85W, 11.1'  
 4" " , N6E, 22.2'

Signed by David B. Babbitt  
 Surveyor's Michigan License No. 21558

Date 8-1-88