

OK B.

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette
(County)

Located In:

Corner Code #

- 1. Public Land Survey T 43N R 25W C-12,C-11,C-13
2. Property Controlling in Section S T R
3. Miscellaneous Property in Sec. S T R

Register of Deeds Stamp & File Number

- 4. Lot No. , Recorded Plat
5. Private Claims

Grid table with columns A-M and rows 2-13. Contains numbers 1-36 in a grid pattern.

I, David B. Babbitt, in a field survey on 5/4, 19 88, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- C-12. West 1/4 cor. of Section 32. Mich. DNR 9/2/69 F. Bray. Set 1" pipe with 4" aluminum cap. 7" aspen, N57E, 14 Lks. 7" balsam, S25E, 22 1/2 Lks.
C-11. NW section corner of Section 32. Mich DNR 9/23/69 F. Bray. Set 1" pipe with 4" aluminum cap. 6" elm, N37E, 15 1/2 Lks. 6" elm, S54E, 37 Lks. 5" elm S72W, 14 1/2 Lks.
C-13. SW section corner of Section 32. Mich. DNR 8-27-69 F. Bray. Set 1" pipe with 4" aluminum cap. 10" elm, N81E, 38 1/2 Lks., 7" h.maple, S50W, 59 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- C-12. Found 1" pipe with 4" aluminum cap. Both of F. Bray's 1969 NBT's are in place but the NE one is a dead stub and the SE one is now a 13" balsam with both blazes completely grown over.
C-11. Found 1" pipe with 4" aluminum cap. All three of F. Bray's 1969 NBT's are in place but all of them are dead and one is down. Marked 4 new NBT's.
C-13. Found 1" pipe with 4" aluminum cap. Both of F. Bray's 1969 NBT's are in place and standing but the elm is dead. Marked 3 new NBT's.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- C-12. DNR Monument 13" balsam, S20E, 14.8' (F. Bray) NBT 7" maple, S36W, 41.8' 6" balsam, N39W, 26.5' 4" balsam, N11E, 20.8'
C-11. DNR Monument 5" h.maple, N34W, 22.3' 6" " , N46E, 12.5' 5" " , S40E, 29.1' 5" " , S15W, 41.7'
C-13. DNR Monument 9" h.maple, S50W, 38.8' (F. Bray NBT) 4" " , S19W, 19.1' 5" balsam, N50W, 28.1' 8" tw.top h.maple, N60E, 18.1'

Signed by David B. Babbitt

Date 8-1-88

Surveyor's Michigan License No. 21558