

0708

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

Marquette  
(County)

Located In:

Corner Code #

- 1. Public Land Survey T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_  
T \_\_\_\_\_ R \_\_\_\_\_
- 2. Property Controlling S 32 T 43N R 25W 11, 4, 8.  
in Section S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_
- 3. Miscellaneous S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_  
Property in Sec. S \_\_\_\_\_ T \_\_\_\_\_ R \_\_\_\_\_

Register of Deeds Stamp & File Number

- 4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
- 5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	16	17	18	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

I, David B. Babbitt, in a field survey on 5/4, 1988, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- 11. SW 1/16 corner of Section 32. No previous record.
- 4. NW 1/16 corner of Section 32. No previous record.
- 8. West 1/16 corner of Section.32. No previous record.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

- 11. Set at the computed center of the SW 1/4 of Section 32 by closed traverse.
- 4. Set at the computed center of the NW 1/4 of Section 32 by closed traverse.
- 8. Set MPOL between the W1/4 corner and the center of Section 32.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- |                         |                           |                       |
|-------------------------|---------------------------|-----------------------|
| 11. DNR Monument        | 4. DNR Monument           | 8. DNR Monument       |
| 8" spruce, S19E, 11.2'  | 10" s.maple, N62W, 31.44' | 9" maple, N25E, 12.5' |
| 14" spruce, S85E, 73.7' | 9" cedar, N16W, 52.50'    | 3" maple, S80E, 13.1' |
| 10" cherry, N37E, 16.1' | 9" y.birch, S54E, 30.33'  | 9" " , S35E, 31.2'    |
| 8" balm , S82W, 61.7'   | 10" s.maple, N57E, 47.50' | 7" " , S31W, 22.3'    |

Signed by David B. Babbitt  
Surveyor's Michigan License No. 21558

Date 8-1-88