

# LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

*Margarette*

| FOR CORNERS OF--                          | LOCATED IN--                       | CORNER CODE NUMBER |
|---|------------------------------------|--------------------|
| 1. PUBLIC LAND SURVEY_____                | T. <u>43</u> N. S. R. <u>25</u> W. | <u>K-2, K-3</u>    |
| 2. PROPERTY CONTROLLING IN SECTION_____   | , T. _____ N. S., R. _____ E. W.   | _____              |
| 3. MISCELLANEOUS PROPERTY IN SECTION_____ | , T. _____ N. S., R. _____ E. W.   | _____              |
| 4. LOT NO. _____, RECORDED PLAT _____     |                                    |                    |
| 5. PRIVATE CLAIMS _____                   |                                    |                    |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Frank J. Bray do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on June 25 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-2 Woodpost:**  
 Tamarack 14 S53°W 8 links  
 Cedar 10 N40°E 32 links  
 Subsequent monument; woodpost
- K-3 Woodpost:**  
 Cedar 18 S56°W 27 links  
 Cedar 14 N53°E 55 links  
 Subsequent monument; woodpost

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-2** This corner was replaced from point of rotted down woodpost. Corner was found by A. Metsa and A. Enger in 1958 Tamarack B.T. to SW had face visible at that time but is now in poor condition.
- K-3** This corner was replaced from 2 Cedar stumps. B.T. to SW has both faces with scribe marks visible. B.T. to NE has been slabbed off but is in the proper position. Corner was found by A. Metsa and A. Enger in 1958.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

**ALL:** 1" iron pipe with 3½" aluminum cap. All bearings are magnetic.

|     |           |      |       |       |       |
|-----|-----------|------|-------|-------|-------|
| K-2 | 6" Cedar  | (48) | (NBT) | N29°E | 25.4' |
|     | 8" Cedar  | (48) | (NBT) | S14°W | 11.2' |
| K-3 | 7" Cedar  | (81) | (NBT) | N02°E | 12.6' |
|     | 12" Cedar | (82) | (NBT) | N43°W | 27.9' |
|     | 13" Cedar | (82) | (NBT) | N88°W | 16.8' |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ CHIEF OF SURVEY PARTY DATE \_\_\_\_\_

APPROVED AND SIGNED BY Frank J. Bray MICHIGAN REGISTERED LAND SURVEYOR DATE 7-8-74  
 (Frank J. Bray) (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575