

✓

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

LAND CORNER RECORD

T. 43. NR. 26. W.

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 3, 4, 9, 10 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 9" Aspen - S 20 W - 6 Links -----

12" Aspen - S 85 E - 9 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by double proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. Swamp edges North and West, as per Gov't. notes, check o.k..

Corner was placed and witnessed April 21, 1953.

SURVEYORS SEAL

SIGNED Dean C. DeWitt DATE 12/2/53  
REGISTERED LAND SURVEYOR