

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T 43 NR 26 W
T 44 NR 26 W

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER 1/4 Corner between Sections 4 & 33 -----

DESCRIPTION OF CORNER MONUMENT 1" Pipe with 4" Brass cap -----

WITNESSES TO CORNER 8" S. Maple - S 3 P - 31 Links -----

8" Elm - S 80 W - 9 Links -----

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was established, by proportionate measurement, by Forestry Division survey crew, while making a partial resurvey of this area. In the absence of any definite original evidence, corner was placed in line, and at proportional distance between the two Section Corners.

Corner was placed and witnessed April 21, 1953.

SURVEYORS SEAL

SIGNED Dean C. Johnson
REGISTERED LAND SURVEYOR

DATE 12/2/53