

2

**MICHIGAN**  
**DEPARTMENT OF CONSERVATION**  
**FORESTRY DIVISION**

**LAND CORNER RECORD**

T 43 N R 26 W  
T 43 NR 27 W

--- Dickinson & Marquette --- COUNTY

DESCRIPTION OF CORNER 1/4 corner between sections 7, T43N R26W and Section 12,

DESCRIPTION OF CORNER MONUMENT 1" iron pipe with 4" brass cap, -----  
T43N R27W

WITNESSES TO CORNER White Birch 8" S 31 W 51 1/2 links, marked 1/4 S NBT

White Birch 6" N 77 W 18 links, marked 1/4 S NBT

Halm of Gilead, 10" S 48 E 16 links, marked 1/4 S NBT

-----  
Distances measured from center of brass cap to NBT notch.

**DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.**

This corner was replaced from one original cedar bearing tree in good condition. Cedar stub N 52 W 20 links, BT face plain with scribe marks plain. Other original cedar bearing tree in poor condition. Stump in place S 45 W 56 links. Old wood post in place. Have good corner 1/2 mile south.  
Corner was found by Pat Byers, Kimberly Clark timber cruiser.

Corner was placed and witnessed on 4 December 1958.

**SURVEYORS SEAL**

*H S Peterson*

SIGNED H. S. Peterson  
REGISTERED LAND SURVEYOR

DATE 12-5-58