

MICHIGAN  
DEPARTMENT OF CONSERVATION  
FORESTRY DIVISION

# LAND CORNER RECORD

T. 43 & 44 N.R. 26 W.

Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to 2 & 3, 43-26 and 34 & 35, 44-26


CORNER MONUMENT 1 inch galvanized pipe with 4 inch brass cap

DATE MONUMENT PLACED AND WITNESSED 4/12/61

WITNESSES TO CORNER..... Tamarack 6" N 57 E 55 Links

Tamarack 9" S 76 E 33.5 Links

Tamarack 7" S 57 W 30.5 Links



AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Set corner from 4 original bearing trees. One cedar (N 44 E 11 links) dry tree, recently gone down shows face distinctly. This tree was up and showed scribe marks just a few years ago when the corner was located. Stumps of other cedar bearing trees have been burned but most still show evidence of face. Three squared posts of various ages had been set within 1 ft. circle of proper location. Random line recently chopped to east starting from this corner by some unknown surveyor. Also old blazed line running north. Corner located by A. Metsa and A. Eger while examining State lands in the area. Corner set with William Oliver.

SURVEYOR'S SEAL

SIGNED

Alice A. Metsa  
REGISTERED LAND SURVEYOR

DATE

4/31/61