

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. 43 N.R. 26 W.


Marquette COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 5, 6, 7 and 8.

CORNER MONUMENT 1 inch galvanized pipe with 4 inch brass cap.

DATE MONUMENT PLACED AND WITNESSED 4/20/61

WITNESSES TO CORNER.....



Hemlock 10" N 73 E 48 Links

Sugar Maple 10" N 66 W 43.5 Links

AND

Elm 9" S 10 W 52 Links

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED. This corner was located by A. Motea while examining lands in the area. Stumps of both bearing trees still in place (cedar and basswood) but quite badly rotted. Faces still show but not scribe marks. Old square cedar post in place. Large maple about 8 ft. east of post has been blazed and registered on by cruisers for the past 50 years or more. Distance north to swamp edge checks, also distance west to top of hill. Corner set by A. Motea and William Oliver.

SURVEYOR'S SEAL

SIGNED

A. Motea
REGISTERED LAND SURVEYOR

DATE

4/24/61