

STATE OF MICHIGAN
DEPARTMENT
OF
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 43 N R 26W

DESCRIPTION OF CORNER Section corner for sections 19/20
30/29

CORNER MONUMENT 1" iron pipe with 4" aluminum cap

DATE MONUMENT PLACED AND WITNESSED 9-27-72 F. J. Bray

WITNESSES TO CORNER..... 6" H. Maple (S19) (NBT) N 50°W, 14.5'



8" Elm (S30) (NBT) S42°W, 20.3'

12" Squared dead aspen, N23°W, 2.8'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was reestablished by double proportioned measurement between

¼ corners ¼ mile to the north, south, and east and pond to the west.

Squared dead aspen near.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray
REGISTERED LAND SURVEYOR
Frank J Bray

DATE 11-16-72