

STATE OF MICHIGAN  
DEPARTMENT  
OF  
NATURAL RESOURCES

LAND CORNER RECORD

Marquette COUNTY


T 43 N R 26 W

DESCRIPTION OF CORNER Section corner for Sections <sup>28/27</sup> 33/34

CORNER MONUMENT 1 1/2" O.D. pipe

DATE MONUMENT PLACED AND WITNESSED June 15, 1972

WITNESSES TO CORNER..... 6" Cedar (NET) S34°W, 6.7'



W. Spruce (NET) N27°W, 7.2'

AND

CIRCLE CORNER REGISTERED

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

This corner was set by using the North 1/16 corner and 1/4 corner between Sections 33/34 double distance and on line. County records state 1/4 corner set mid-point and on line between the section corners to the north and to the south. North 1/16 set mid-point and on line between the section corner to the north and 1/4 corner to the south.

SURVEYOR'S SEAL

DISTRIBUTION:

Forestry Division, Lansing

SIGNED

Frank J. Bray  
REGISTERED LAND SURVEYOR  
Frank J. Bray

DATE

8-11-72