

Marquette Co

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>25</u> T. <u>43</u> N. S., R. <u>26</u> E. W.		<u>K-10</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on June 18 19 79, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

West  $\frac{1}{2}$  corner; Wood post, Tamarack 18 - S25°W - 11 lks.; Cedar 12 - N43°E - 9 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

Found old 3" x 3" square Cedar post - stumps for both O.B.T.S. exact and showing old scars but too burned and rotted for scribe marks. Old blazed Cedar stub 5.2' S21°E from corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

1" pipe, 4" aluminum cap; 6" Cedar - S8°W - 15.2'; 4" Tamarack - S76°W - 6.95'; 9" Cedar - N71°W - 14.75'; 5" Cedar - N21°W - 13.9'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt CHIEF OF SURVEY PARTY MICHIGAN REGISTERED LAND SURVEYOR DATE 6-25-79 (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558