

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF-- | LOCATED IN-- | CORNER CODE NUMBER |
|---|--|--------------------|
| 1. PUBLIC LAND SURVEY_____ | T. <u>43</u> N. <u>26</u> E. R. <u>26</u> W. | <u>M-2, K-1</u> |
| 2. PROPERTY CONTROLLING IN SECTION <u>1</u> | , T. <u>43</u> N. <u>26</u> E. R. _____ W. | <u>14</u> |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____ | , T. _____ N. _____ E. R. _____ W. | _____ |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

Frank J. Bray

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on May 22 1974, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

M-2 Woodpost:
 Sugar 14" 868°E 25 links
 Y. Birch 15" N16°W 12 links

K-1 Woodpost:
 Sugar 22" N45°E 41 links
 Fir 8" N57°W 20 links
 Y. Birch 30" S54°W 44 links
 Sugar 28" S26°E 80 links

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

M-2 This corner was placed on line and the single proportioned measurement between the town corner to the north and section corner to the south.

K-1 This corner was placed on line and the single proportioned distance between $\frac{1}{4}$ corner $\frac{1}{4}$ mile to west and town corner 1 mile to east woodpost and blazed trees near.

14 This corner was placed midway and on line between the section corner to the south and $\frac{1}{4}$ corner to the north. Woodpost near.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-1: 1" iron pipe. All others 1" iron pipe with $\frac{1}{4}$ " aluminum cap. All Bearings are magnetic.

| | | | | |
|------------|--------------------|-------|-------|-------|
| M-2 | 9" Elm (48) | (NBT) | N64°E | 29.9' |
| | 10" Elm (48) | (NBT) | S01°E | 22.5' |
| K-1 | 16" Elm (81) | (NBT) | S33°E | 14.9' |
| | 9" Cedar (836) | (NBT) | N38°E | 31.5' |
| 14 | 5" Balsam (8 1/16) | (BT) | N77°E | 14.5' |
| | 7" Balsam (8 1/16) | (BT) | S27°W | 12.1' |

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ CHIEF OF SURVEY PARTY DATE _____

APPROVED AND SIGNED BY Frank J. Bray MICHIGAN REGISTERED LAND SURVEYOR DATE 6-10-74
 (Frank J. Bray) (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 13575