

LAND CORNER RECORDATION CERTIFICATE

MARQUETTE
CO.

FILING REQUIREMENT OF ACT 74, MICH. P.A. 1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 ^{N.} _{S.} , R. 26 ^{W.} _{E.}	I-8, I-9
2. PROPERTY CONTROLL- ING IN SECTION _____	, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____, N. _____, S. _____, R. _____, E. _____, W. _____	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on December 10 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- I-8 East 1/4 corner - Section 22; Wood Post, 10" Tam. - S65°E - 27 lks.; 10" Spruce - N56°W - 26 lks.
- I-9 S.E. section corner of Section 22; Wood Post, Y. Birch 22" - S18°W - 21 lks., Cedar 28" - N42E - 21 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- I-8 Found old square post S.E. tam. O.B.T. down and in poor condition but scribing still legible. Replaced post with D.N.R. Mon. Set new cedar post beside it.
- I-9 Found square cedar post with a very large cedar stump in the right position for the N.E. O.B.T. This stump is burned and center completely gone; no sign of the original face but it does have a definite face made at some time after the tree was dead.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- I-8 D.N.R. Mon.; 10" Cedar - S53°W - 21.6'; 8" Cedar - N34°W - 23.6'; 11" Cedar - N20°E - 40.4'; 9" Cedar - S64°E - 41.4'.
- I-9 D.N.R. Mon.; 4" Balsam - S21°E - 6.9'; 10" Spruce - N48°E - 11.15'; 15" Cedar - N40°E - 28.3'; 6" Balsam - N71°W - 14.7'.

SIGNED BY

David B. Babbitt

DATE 12-17-1981

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)