

LAND CORNER RECORDATION CERTIFICATE

MARQUETTE
CO.

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 N. R. 26 E. W.	J-9, K-8
2. PROPERTY CONTROLLING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on December 14 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- 9 South 1/4 corner of Section 23; Wood Post, Y. Birch 30" - N26°W - 35 lks.; Elm 36" - S44°E - 56 lks.
- 8 East 1/4 corner of Section 23; Cedar Post, Spruce 12" - S44°W - 50 lks.; Cedar 12" - N58°E - 20 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- 9 Set M.P.O.L. between the S.W. and S.E. section corners of Section 23. No sign of O.B.T.s. Stream Call 20.60 Chs. East fits well.
- 8 Found Sq. Cedar Post with a down cedar in position for the N.E. O.B.T. It is quite rotten but shows evidence of both upper and lower face.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- 9 1" pipe, 4" aluminum cap; 17" Balsam - N36°E - 71.0'; 14" Balsam - N44°E - 67.9'; 4" W. Spruce - N31°E - 41.6'; 5" Balsam - N5°W - 73.5'.
- 8 D.N.R. Mon.; Old N.B.T.s; 13" Cedar - S76°W - 3.2'; 11" Cedar - N15°W - 14.7'.
NEW ; 5" Cedar - S43°W - 15.75'; 11" Cedar - N57°E - 61.4'.

SIGNED BY _____

David B. Babbitt

DATE _____

12-17-1981

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)