

MARQUETTE
CO

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY_____	T. 43 N. S., R. 26 E. W.	K-9, L-9
2. PROPERTY CONTROLL- ING IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION_____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on December 10 1981, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- K-9 S.W. corner of Section 24; Wood Post, Cedar 26" - N41°W - 33 lks.; DO 30" - S21°E - 22 lks.
- L-9 South 1/4 corner of Section 24; Cedar Post Tam. 18" - N44°W - 30 lks., Cedar 10" - S25°E - 28 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- K-9 Set by double proportion using 1/4 corners, 1/2 mile north, 1/2 mile east and 1/2 mile south and the section corner 1 mile west. No sign of O.B.T.s.
- L-9 Set from 20" Tam. Stump N44°W - 30 lks. Too rotten and weathered for marks, but it is the only Tam. Stp. of proper size within reasonable distance and there are fragments of a cedar in the approx. position for the S.E. O.B.T. Swamp calls 1-1/2 chs. west and 9 chs. east fit very well, and is only 7.5' from a proportioned position. Also using this position, a large cedar with line blazes on the E. and W. sides, falls on line less than 100' E. By counting the growth rings this cedar was determined to have been marked between 1900 and 1910.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- K-9 1" pipe, 4" aluminum cap; 4" Spruce - N45°E - 30.0'; 9" Balsam - S50°E - 26.4'; 5" Spruce - S73°W - 20.8'; 6" Spruce - N3°W - 13.5'.
- L-9 1" pipe, 4" aluminum cap; 14" Cedar - N10°W - 16.25'; 10" Cedar - N68°E - 10.8'; 5" Cedar - S27°W - 4.0'; 4" Cedar - N64°W - 22.3'.

SIGNED BY

David B. Babbitt

DATE

12-17-1981

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558

(SEAL)