

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Marquette</u> <small>(County)</small>	Located In:	Corner Code ##
1. Public Land Survey	T <u>43N</u> R <u>26W</u>	<u>E-7.</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	16		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, David Babbitt, in a field survey on 10/31, 19 86, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

E-7. SE section corner of Section 17. Cedar post. OBT's Cedar 16 - N75E, 28 Lks.
 DO 18 - S34W, 36 Lks.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

E-7. Found sq. cedar post set by Art Enger, RLS, in 1958. Post was set from SW. Original bearing tree discovered by Mr. Enger dead but standing with blazes showing axe marks but no scribing visible. Said OBT is now down but with blazes and axe marks still plain. Set DNR monument in place of Enger's post.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-7. DNR monument.
 7" spruce S81W, 27.0'
 9" cedar S42E, 32.3'
 7" cedar N23E, 43.1'
 11" cedar N65W, 13.5'

Signed by David B. Babbitt Date 1-27-87
 Surveyor's Michigan License No. RLS 21558