

MICHIGAN
DEPARTMENT OF CONSERVATION
FORESTRY DIVISION

LAND CORNER RECORD

T. ~~44-45~~ NR 23 W. . .

----- Marquette ----- COUNTY

DESCRIPTION OF CORNER Section Corner common to Sections 3-4-33-34 -----

DESCRIPTION OF CORNER MONUMENT 1" pipe with 4" brass cap -----

WITNESSES TO CORNER 8" Cedar N 69° E 52 links
"S34 NBT"

7" Cedar S 45° E 36 1/2 links
"S3 NBT"

7" Cedar N 4° W 52 links
"S33 NBT"

DESCRIPTION IN DETAIL AS TO HOW CORNER WAS LOCATED AND IDENTIFIED OR RESTORED.

Replaced Sec. Cor. from one B. Ash B.T. bearing N 70° W 35 links.
Tree green, with rotted center.
Numerous blazes in vicinity.

(Found tamarack line tree as per Gov't notes, 4.15 chs west of this corner. Line tree dead but standing. Marked with two notches on both East and West sides)

Found corner with Art Enger, Ass't Forester.

SURVEYORS SEAL

SIGNED Billy D. Buckler DATE 3/6/57
REGISTERED LAND SURVEYOR