

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____ T. <u>44</u> N. S., R. <u>23</u> E. W.		<u>L-1, M-1, M-2</u>
2. PROPERTY CONTROLLING IN SECTION _____ T. _____ N. S., R. _____ E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____ T. _____ N. S., R. _____ E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, David B. Babbitt do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram - over) were, in a field survey on August 21 1979, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_ 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

- L-1 North 1/4 corner - Sec. 1; Wood Post, Cedar 16 - N40°E - 12 lks.; Hemlock 15 - N36°W - 40 lks.
- M-1 N.E. section corner - Sec. 1; Wood Post, Hemlock 18 - N46°W - 27 lks.; Hemlock 16 - S27°E - 23 lks.
- M-2 East 1/4 corner - Sec. 1; Hemlock 9" for 1/4 corner; Cedar 8 - S26°E - 16 lks.

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- L-1 Found remains of N.E. Cedar O.B.T. down and quite rotten but part of upper face and very plain scribing "1/4" - roots of N.W. Hemlock O.B.T. in place bearing & distance exact.
- M-1 Set from two hemlock stumps, very rotten, bearings and distances fit exactly for both O.B.T.s. Measurements to stream West and South fit G.L.O. record & distances to 1/4 corners 1/2 mile south and 1/2 mile west fit well.
- M-2 Found remains of Hemlock tree blowdown very rotten but definitely had been squared - Cedar stump in place S26°E - 10.6' for O.B.T. - very large W.P. stump on line 832' S. for 40" W.P. line tree.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- ALL - 1" pipe, 4" aluminum cap.
- L-1 - 7" Cedar - 835°W - 16.0'; 6" Cedar - N39°W - 35.6'; 4" Y. Birch - N54°E - 18.35'; 6" Cedar - S65°E - 2.9'.
- M-1 - 11" Hemlock - N37°W - 23.5'; 4" Hemlock - N61°E - 12.6'; 13" Hemlock - S89°E - 29.6'; 10" Cedar - S33°W - 29.75'.
- M-2 - 14" Hemlock - S33°E - 19.35'; 8" Cedar - S58°W - 36.6'; 6" Y. Birch - N38°W - 14.45'; 14" Hemlock - N34°E - 43.1'.

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY David B. Babbitt DATE 1-22-80  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 21558